

**TECHNICAL SPECIFICATION 110
BORROW**

110.1 SCOPE OF WORK

This technical specification covers the furnishing of all labor, materials, tools, testing, and equipment necessary to properly place borrow material at all locations where shown on the drawings or as ordered by the Engineer.

110.2 MATERIALS

All materials used under the title of Borrow shall conform to Form 816, Section 2.07. Recycled/reclaimed material shall not be used unless approved by the Engineer.

110.3 CONSTRUCTION METHODS

Borrow will be permitted only to the extent necessary to complete the embankments and similar details and only after all usable material from the excavation has been placed. With the approval of the Engineer, the Contractor may be permitted to place borrow before the excavation is completed, but will be held responsible for the proper placing of all suitable excavated material, and no payment will be allowed for any borrow placed in lieu of suitable excavated material. This permission may be revoked by the Engineer at any time if in his opinion satisfactory progress is not maintained on other operations.

The Contractor shall notify the Engineer at least 2 days prior to obtaining any borrow material, and shall provide to the Engineer all testing reports of said material from a testing laboratory certified in the State of Connecticut.

Borrow compaction, if necessary, shall be performed with equipment and by methods approved by the Engineer.

110.4 MEASUREMENT

Measurement for this item will be based on number of cubic yards compacted and accepted in place where shown on the drawings or as ordered by the Engineer.

110.5 PAYMENT

Payment for this item will be based on the contract unit price per Cubic Yard complete, compacted and accepted in place, including all labor, materials, tools, testing, and equipment necessary to complete the work as specified.

PAY ITEM	PAY UNIT
Borrow	C. Y.